



KHYBER PAKHTUNKHWA CITIES IMPROVEMENT PROJECT
PROJECT MANAGEMENT AND CONSTRUCTION SUPERVISION CONSULTANTS
MINCONSULT SDN BHD
JOINT VENTURE
CREATIVE ENGINEERING CONSULTANTS



Date: 31st July 2023

Ref: KPCIP/PMSCS/RE/ATD/LOT-1/108

The Chief Executive Officer
Water and Sanitation Services Company
Abbottabad

Project: KHYBER PAKHTUNKHWA CITIES IMPROVEMENT PROJECT (KPCIP):
OCB/KPCIP/CW-01: Development of Urban / Green Spaces and Parks: Lot-1:
Pedestrianization of Market in Old City Centre; and Urban / Green Space Initiatives
- Sherwan Adventure Family Park, Abbottabad.

Subject: Bunching of Electric Cables in the Bazar.

Reference: 1. Your Letter no: CEO/WSSCA/023/8837

Dated: 12th July 2023

In reference to your above letter, I am writing to address the concerns raised regarding the bunching of electrical cables without proper design. I would like to clarify that the bunching item 4.1 involves the bundling and securing of cables with the wall, taking into account the existing site conditions. As the existing shops are not vertically and horizontally aligned, adjustments are necessary to accommodate the site's unique layout. The shop drawings have been prepared and appropriately signed by the site staff. They are hereby attached for your reference and information.

Regarding the issue of poorly clamped cables, I want to mention that in certain areas, we refrained from clamping the cables due to their current use. We have already requested approval for a WAPDA NOC (No Objection Certificate) to proceed with the necessary work. Once the NOC is granted, WAPDA will switch off the power, allowing the contractor to remove the old cables and properly clamp the new ones. This process will be carried out in the mentioned location where the bunching is not yet finalized and requires improvement after the old cables are removed.

To provide further clarity, I have attached some pictures depicting the finalized bunching of electrical cables in other areas. Rest assured, we are actively working to address the concerns raised and will ensure that the electrical cable bunching is executed with utmost precision and adherence to safety standards.

Attachment:

1. Shop Drawing
2. Pictorial Evidence

Yours Sincerely,

Engr. Muhammad Shoaib
The Engineer/Resident Engineer
PMSCS-KPCIP
Green Urban Spaces project Abbottabad.

Handwritten notes:
- L.E (SWM)
- Review and share comments
- Draft response, if further correspondence is required
- AM/Planning
- FYI J.N.A.
- 28-8-23

Page 1 of 2

PMSCS Office Abbottabad: House # 82/3 Hill Road, Near AMC Mess Abbottabad, KPK, Pakistan
Phone & Fax 0992-330141, Email ID: reatd.kpcip16@gmail.com